

**From:** [Debra M. Beckwith](#)  
**To:** [BR](#)  
**Subject:** Bridge Advertisement (DSI 23-006) Rescind approved F\* values for MSE walls  
**Date:** Monday, March 13, 2023 10:56:06 AM

---

The [EPG](#) and [Bridge Standard Drawings](#) have been updated as described below:

**Implementation Statement: Effective for June 2023 letting.**

*(The Implementation Statement is a recommendation by the Development Section. The SPM is responsible for the level of implementation for any particular job.)*

Revision Date	Items Revised	Description of Change
<a href="#">Mar. 2023</a>	EPG: <a href="#">751.50</a>	Backfill materials used in the previously submitted product specific F* test reports are not currently representing MoDOT select granular backfill material so rescinding previously approved F* values.
	Bridge Standard Drawings: <a href="#">MSEW_01</a>	
	MicroStation Cells: NA	<ul style="list-style-type: none"> <li>For projects let after June 1, 2023, the AASHTO default values shall be used for the pullout friction factor in accordance with figure 5.8.5.2A of the Standard Specifications for Highway Bridges, 17th Edition for ASD or figure 11.10.6.3.2-2 of the LRFD Bridge Design Specifications, 9th Edition for LRFD.</li> </ul>
	Std. Specifications: NA	
	Standard Plans: NA	
	Bridge Special Provisions: NA	

Follow links above for more information, or to view more details about this (or any) revision, use the [Revision Index Database](#), located under Completed Revisions on Development’s Sharepoint page.

Instructions:

- Under Tables (left-hand side) double-click on RevisionRecords.
- Click on the link under the Effective Date to access documentation for the completed revision.

*Debra M. (Debbie) Beckwith*

Structural Specialist – Development Section

**Missouri Department of Transportation**

Central Office – Bridge Division

105 W. Capitol Ave., P.O. Box 270, Jefferson City, MO 65102

573-522-8718

[www.modot.org](http://www.modot.org)